



Estimate

Date: 11/26/2018

Estimate #: 1697

P.O. No.: Sauer

**60102 Cinder Butte Road
Bend, OR 97702
CCB# 216026**

CLIENT:

Collabrich Hybridesign
Miriah O'Dair
541-788-3841
collabrich@gmail.com

Description	Qty	Rate	Total
<p>OPTION 1 - POST MOUNTED GRAB RAILING SYSTEM - Material and labor to fabricate, powder coat and install two grab rails approximately 13' each. Grab railing will feature a 1.5" round tube grab rail supported by 5 1.5" square steel tube posts core drilled and wet-set in mortar into existing paver steps and sidewalk. **FINISHED RAIL HEIGHT: 36" ABOVE GRADE** **PRODUCT WILL BE SAND BLASTED AND POWDER COATED SHERWIN WILLIAMS MATTE BLACK** **SUBJECT TO SITE CONDITION VERIFICATION - ADDITIONAL CHARGES MAY APPLY** **OTHERWISE SIMILAR TO CUSTOMER SUPPLIED RENDERINGS**</p>	1	4,112.21	4,112.21

Work authorization: _____... Total

If you are in agreement with the estimate, please review and sign the attached Consumer Protection notice as well as the Contractors Right to Lien Documents. These forms are required by both the State of Oregon Construction Contractors Board and Iron Environments. This is a legal and binding contract. By signing this estimate you have contracted with Iron Environments for their above described services, and that a lien may be claimed under ORS 87010 for all materials and labor furnished if this account is placed in the hands of an attorney for collection, the purchaser agrees to pay reasonable collection costs, including attorney's fees, even though no suit or action is filed, however, if suit or action is filed, the amount of such attorney's fees shall be fixed by the court or courts in which the suit is tried, heard or decided.



Estimate

Date: 11/26/2018

Estimate #: 1697

P.O. No.: Sauer

**60102 Cinder Butte Road
Bend, OR 97702
CCB# 216026**

CLIENT:

Collabrich Hybridesign
Miriah O'Dair
541-788-3841
collabrich@gmail.com

Description	Qty	Rate	Total
<p>OPTION 2A - POST MOUNTED GRAB RAILING SYSTEM WITH BALUSTRADE AND BALUSTERS - Material and labor to fabricate, powder coat and install two grab rails approximately 18' each. Grab railing will feature a 1.5" round tube grab rail supported by 6 1.5" square steel tube posts core drilled and wet-set in mortar into existing paver steps and sidewalk. Railing on sidewalk will feature a 1.5" round tube balustrade and alternating pattern of 1/2" round tube and 3/4" square tube balusters.</p> <p>**FINISHED RAIL HEIGHT: 36" ABOVE GRADE**</p> <p>**PRODUCT WILL BE SAND BLASTED AND POWDER COATED SHERWIN WILLIAMS MATTE BLACK**</p> <p>**SUBJECT TO SITE CONDITION VERIFICATION - ADDITIONAL CHARGES MAY APPLY**</p> <p>**OTHERWISE SIMILAR TO CUSTOMER SUPPLIED RENDERINGS**</p>	1	5,982.92	5,982.92

Work authorization: _____... Total

If you are in agreement with the estimate, please review and sign the attached Consumer Protection notice as well as the Contractors Right to Lien Documents. These forms are required by both the State of Oregon Construction Contractors Board and Iron Environments. This is a legal and binding contract. By signing this estimate you have contracted with Iron Environments for their above described services, and that a lien may be claimed under ORS 87010 for all materials and labor furnished if this account is placed in the hands of an attorney for collection, the purchaser agrees to pay reasonable collection costs, including attorney's fees, even though no suit or action is filed, however, if suit or action is filed, the amount of such attorney's fees shall be fixed by the court or courts in which the suit is tried, heard or decided.



Estimate

Date: 11/26/2018

Estimate #: 1697

P.O. No.: Sauer

**60102 Cinder Butte Road
Bend, OR 97702
CCB# 216026**

CLIENT:

Collabrich Hybridesign
Miriah O'Dair
541-788-3841
collabrich@gmail.com

Description	Qty	Rate	Total
<p>OPTION 2B - POST MOUNTED GRAB RAILING SYSTEM - Material and labor to fabricate, powder coat and install two grab rails approximately 18' each. Grab railing will feature a 1.5" round tube grab rail supported by 6 1.5" square steel tube posts core drilled and wet-set in mortar into existing paver steps and sidewalk.</p> <p>**FINISHED RAIL HEIGHT: 36" ABOVE GRADE**</p> <p>**PRODUCT WILL BE SAND BLASTED AND POWDER COATED SHERWIN WILLIAMS MATTE BLACK**</p> <p>**SUBJECT TO SITE CONDITION VERIFICATION - ADDITIONAL CHARGES MAY APPLY**</p> <p>**OTHERWISE SIMILAR TO CUSTOMER SUPPLIED RENDERINGS**</p>	1	5,732.72	5,732.72

Work authorization: _____... **Total** \$15,827.85

If you are in agreement with the estimate, please review and sign the attached Consumer Protection notice as well as the Contractors Right to Lien Documents. These forms are required by both the State of Oregon Construction Contractors Board and Iron Environments. This is a legal and binding contract. By signing this estimate you have contracted with Iron Environments for their above described services, and that a lien may be claimed under ORS 87010 for all materials and labor furnished if this account is placed in the hands of an attorney for collection, the purchaser agrees to pay reasonable collection costs, including attorney's fees, even though no suit or action is filed, however, if suit or action is filed, the amount of such attorney's fees shall be fixed by the court or courts in which the suit is tried, heard or decided.